Abstract Notification dated 23rd—25th October 1930.

The attention of the public is invited to the detailed notification, calling for sealed tenders for laying 4" cast iron delivery and distribution pipes for Water Supply to the Northern Extension and Kuripalya at Tumkur published on page 1350 of Part VI of the *Mysore Gazette*, dated 30th October 1930.

The last day for the receipt of tenders is 14th November 1930.

M. NARASIMHAIYA,
Executive Engineer.

KOLAR DIVISION.

Notice dated 28th October 1930.

The attention of the public is invited to the Notification published in the *Mysore Gazette*, Part VI, pages 1377 and 1378, calling for tenders for Resorting Thimmnahalli Kanivekere Reg. No. 858, Bagepalli Taluk

The latest date for tender is 25th November 1930.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Notification dated 25th October 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 24th November 1930 (3 P.M.), for restoring Neglal Tank, Reg. No. 232 of Koratagere Taluk, Tumkur District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of December 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M., on working days.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Negeal Tank, Reg. No. 232 of Koratagere Taluk, Tumkur District" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender of the successful competitor will be required to execute the usual bond in defaults of which his tender will be cancelled and earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates, measurements quality of work, etc., and in all disputes of any kind, the decision of the Chief Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lump sum provisions are subject to modifications as per data worked out during execution. For individual items of work under lumpsum provisions the rates tendered for similar items of works will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

Abstract of estimate of quantities for Restoring Neglal Tank, Registered No. 282 of Koratagere Taluk, Tumkur District :—

Sl. No.	Items of work	Quantity	Per	Rate in figures	Rate in words	Cost
	Bund R. L. 57·00.			Rs. a. p.		
1	Clearing jungle	6	Grade			
2	Cutting grips in old bund ...	168	R.yd.			
3	Earthwork to bund including lead, lift, watering and tamping, etc., complete.	520	C.yd.			
4	Turfing ...	705	S yd.			
5	Rough stone work new ...	10	C.yd.			
6	Providing and fixing grade stones including cutting figures and painting, etc., complete.	7	Each			
7	Providing and fixing B. M. stones ...	2	,,			
8	Do Register No. stone	1	,,			
	Breach.					
1	Clearing jungle ...	Lump	sum			
2	Do silt ...	1,212	C.yd.			
3	Cutting grips on slopes of old bund ...	308	R.yd.			
4	Burnt brick in surki mortar-core wall ...	113	C.ft.			
5	Earthwork to bund including watering and tamping.	3,883	C.yd.			
6	Turfing ...	489	S.yd.			
7	Removing and stacking old stones of apron.	51	C.yd.			
8	New stone revetment ...	351	,,			
9	Old stone work with new jelly ...	51	,,			
10	Dismantling the old body wall ...	Lump	sum			
11	Unforeseen charges such as removing boulders, etc.	Lump	sum			
	Sluice at R. L. 40·00.					
1	Eearthwork excavation cut opening the bund.	422	C.yd.			
2	Removing and resetting old stone revetment.	25	,,			
3	New stone revetment ...	13	,,			
4	Concrete in surki mortar ...	210	C.ft.			
5	Burnt brick in surki mortar ...	676	,,			
6	Burnt stone slabs roughly dressed and fiixed 6" thick.	333	S.ft.			
7	Surki plastering ...	10·89	Sqr.			
8	Cement pointing ...	9·03	,,			
9	Providing wooden plug and iron rod ...	Lump	sum			
10	Boring holes in slab ...	3	each			
11	Refilling with available earth including watering and tamping.	464	C.yd.			
12	New stone work for lead off channel ...	7	,,			
	Waste Wier at R. L. 50·00.					
1	Earthwork excavation ...	1,351	C.yd.			
2	Do to flank bund, watering and tamping using the earth got from approach.	464	,,			
3	Concrete in surki mortar ...	71	,,			
4	Burnt brick in surki mortar ...	348	,,			
5	Burnt stone slabs roughly dressed and fixed 6" thick.	73	S.ft.			
6	Plastering with surki mortar ...	5·77	Sqr.			
7	Cement pointing ...	0·53	,,			